

350-2023 ADDENDUM 2

MCLEOD CREEK DRAINAGE IMPROVEMENTS

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: May 23rd, 2023
BY: Tristan Eldridge, C.E.T.
TELEPHONE NO. 204-896-1209

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, **May 26, 2023**.

QUESTIONS AND ANSWERS

- Q1:** Regarding the open cut installation of the 1200x600 box culvert on Essar Avenue are temporary water services required?
- A1:** Yes, temporary water services will be required for the 13 houses that will be affected by these works, should existing shutoff valves be used to isolate the portion of watermain in the work area. An alternative would be to cut and cap the water main on either side of the excavation. Temporary water supply or cutting and capping of the water main is considered incidental to the pipe cost.
- Q2:** Regarding the open cut installation of the 1200x600 box culvert on Essar Avenue will Hydro or MTS be relocating their utilities prior to construction?
- A2:** No, the Contractor will be required to support these utilities within the excavation throughout construction as per E29.
- Q3:** Regarding the open cut installation of the 1200x600 box culvert on Essar Avenue what flows should be assumed for by-pass pumping for the 200mm WWS?
- A3:** Provide pumps to support by-pass pumping assuming a full 200mm gravity pipe and as per E28.