



### 383-2023 ADDENDUM 3

#### SUPPLY AND INSTALLATION OF NEW PVC SWIMMING POOL MEMBRANE AND ASSOCIATED WORKS – 2015 MAIN STREET

### URGENT

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
BID/PROPOSAL**

ISSUED: August 24, 2023  
BY: Lou Chubenko  
TELEPHONE NO. 204 470-7881

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID/PROPOSAL AND SHALL FORM  
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

### PART D – SUPPLEMENTAL CONDITIONS

- Revise: D2.2(g) to read: Application of new 60 mil. PVC pool membrane at pool tank floors, walls and **beach ramp entry**, terminations to be at top of pool walls below coping, as per manufacturers specifications and written instructions.
- Revise: D2.2(m) to read: To supply and install depth markings, **racing lanes** and demarcation lines on vertical walls and pool base floor at required points, **in conformance to Manitoba Health Swimming Pools and Other Water Recreational Facilities Regulation (MR 132/97).**

### PART E – SPECIFICATIONS

- Revise: E4.2.3 to read: Provide 2' x 2' mock samples of 60 mil PVC membrane (**for smooth and anti-slip surfaces**) and 11 oz. **geotextile underlayment felt**, PVC coated stainless steel, countersunk flange fasteners, markings and **racing line samples (for smooth and anti-slip surfaces)** and 1' x 1' mock sample of adhesive attaching the PVC to the felt under layer. **Prior to ordering of pool membrane materials by the Contractor, the samples (textures, colors, model numbers, etc.) must meet the approval of the Contract Administrator.**
- Revise: E4.7.1 to read: **Acceptable Products:** RenoSys Incorporated Endura Series polyester reinforced 60 mil. PVC pool membrane system **or CGT Infinity polyester reinforced 60 mil. PVC pool membrane system.** Reinforcing shall be non-wicking polyester scrim fabric 1000 Denier yarn 9 x 9 per inch count, in accordance with Bidding Procedures Clause B7. Substitutes.
- Revise: E4.7.3 to read: Pool lining membrane shall be flexible roll goods 65" wide x 25 meters long x 60 mil thick, 100% virgin 3-ply PVC material, fully UV and chlorine stabilized, reinforced with a wick proof scrim. Reinforcing scrim shall consist of a tightly woven polyester 9 x 9 thread spacing per inch, 1,000 Denier thread for tear and puncture resistance. The scrim shall be offset approximately 3/4" from the edge and shall be fully machine edge encapsulated. **The material shall be applied with slip-resistant textured surfaces on the beach entry ramp and stairs (if applicable) – refer to Drawing S02 and Drawing S04. The pool floor and wall areas to be provided with smooth surfaces.** All welds shall be accomplished using hot-air welding. A continuous air entrapment weld shall be applied on all welds, and then a minimum 3/4" wide final weld shall be installed.

Revise: E4.7.3 k) to read: Contractor shall provide O&M manuals, PVC underwater patch kit, and additional or extra 60 mil PVC membrane and 11 oz. felt material for maintenance purposes **(1 complete roll of each – 65” wide by 82’ long)**.