PLANT SCHEDULE

TREES	CODE	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	QTY
	AH	ALNUS HIRSUTA 'HARBIN'	PRAIRIE HORIZON® MANCHURIAN ALDER	60MM CAL.	B&B	2
	FN	FRAXINUS NIGRA 'FALLGOLD'	FALLGOLD ASH	60MM CAL.	B&B	2
	LL	LARIX LARICINA	TAMARACK	250CM HT.	B&B	1
	QP	QUERCUS ELLIPSOIDALIS 'DURMARG'	SHOOTING STAR™ NORTHERN PIN OAK	60MM CAL.	POT	4

SHRUBS	CODE	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	SPACING	QTY
	auu	ARCTOSTAPHYLOS UVA-URSI	KINNIKINNICK	1 GAL.	POT	0.3m	64
	JI	JUNIPERUS HORIZONTALIS 'LIMEGLOW'	LIMEGLOW CREEPING JUNIPER	3 GAL.	POT	1m	9

HERBACEOUS	CODE	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	SPACING	QTY
FOR INFORMATION ONLY: HERBACEOUS PLANTINGS TO BE SUPPLIED AND INSTALLED BY THE DOWNTOWN WINNIPEG BIZ							
		MEDICINAL GARDEN MIX					21.5 m²
	amf	ACHILLEA MILLEFOLIUM	COMMON YARROW	1 GAL.	POT	2% @ 300mm	5
	agf	AGASTACHE FOENICULUM	BLUE GIANT HYSSOP	1 GAL.	POT	8% @ 450mm	9
	auu	ARCTOSTAPHYLOS UVA-URSI	KINNIKINNICK	1 GAL.	POT	2% @ 300mm	5
	alv	ARTEMISIA LUDOVICIANA	PRAIRIE SAGE	4.5"	POT	1% @ 300mm	3
	aic	ASCLEPIAS INCARNATA	SWAMP MILKWEED	4.5"	POT	5% @ 300mm	13
	ana	ASTER NOVAE-ANGLIAE	NEW ENGLAND ASTER	4.5"	POT	2% @ 300mm	5
	fos	FESTUCA OVINA SAXIMONTANA	SHEEP FESCUE	4.5"	POT	11% @ 300mm	28
	fvg	FRAGARIA VIRGINIANA SSP. GLAUCA	WILD STRAWBERRY	4.5"	POT	7% @ 300mm	18
	hrc	HEUCHERA RICHARDSONII	PRAIRIE ALUM ROOT	4.5"	POT	5% @ 300mm	13
	hod	HIEROCHLOE ODORATA	SWEETGRASS	1 GAL.	POT	25% @ 750mm	10
	mft	MONARDA FISTULOSA	BERGAMOT	4.5"	POT	5% @ 600mm	4
	rht	RUDBECKIA HIRTA	BLACK-EYED SUSAN	1 GAL.	POT	5% @ 350mm	10
	scd	SOLIDAGO CANADENSIS	GOLDENROD	1 GAL.	POT	2% @ 300mm	5
	snt	SORGHASTRUM NUTANS	INDIAN GRASS	1 GAL.	POT	18% @ 450mm	20
	zar	ZIZIA AUREA	GOLDEN ALEXANDER	4.5"	POT	2% @ 300mm	5
	alv	ARTEMISIA LUDOVICIANA	PRAIRIE SAGE	4.5"	POT	300mm	41
	nrt	NICOTIANA RUSTICA	AZTEC TOBACCO	1 GAL.	POT	600mm	4

LEGEND

- PROPERTY LINE
- LIMIT OF CONSTRUCTION
- EXISTING OVERHEAD HYDRO LINE
- EXISTING SANITARY LINE
- EXISTING STORMWATER LINE
- PROPOSED SUBDRAIN
- PROPOSED SITE LIGHTING CONDUIT
- CONCRETE PAVING
- STABILIZED AGGREGATE PAVING
- WOOD MULCH SURFACING
- SOD REPAIR
- IN-GROUND WASTE BINS
- EXISTING DECIDUOUS TREE
- EXISTING CONIFEROUS TREE

PLANTING NOTES

1. ALL PLANTING AND INSTALLATION IN RIGHT OF WAY SHALL MEET LOCAL MUNICIPAL STANDARDS AND SPECIFICATIONS.
2. LANDSCAPE CONTRACTOR SHALL COORDINATE HIS WORK WITH OTHER CONTRACTORS ON SITE TO MINIMIZE DAMAGE TO COMPLETED LAWN AND PLANT MATERIAL INSTALLATION.
3. IF ANY DISCREPANCY EXISTS BETWEEN THE QUANTITIES, SIZES OR MATERIALS INDICATED ON THE PLAN AND SHOWN IN THE PLANT LIST, THE PLAN SHALL GOVERN.
4. IT IS THE LANDSCAPE CONTRACTORS RESPONSIBILITY TO VISIT THE SITE PRIOR TO START OF WORK, TO BECOME FAMILIAR WITH EXISTING CONDITIONS AT THE SITE.
5. CONTRACTOR IS RESPONSIBLE FOR ROUGH GRADING OF SUBGRADE BELOW LAWN AND LANDSCAPE AREAS.
6. CONTRACTOR IS RESPONSIBLE FOR RESPREADING TOPSOIL, FINE GRADING AND PREPARATION OF ALL LAWN AND LANDSCAPE AREAS.
7. LANDSCAPE CONTRACTOR SHALL PROVIDE SOIL TEST ANALYSIS FOR ALL SOIL USED ON PROJECT. COPIES OF SOIL ANALYSIS SHALL BE PROVIDED TO LANDSCAPE ARCHITECT PRIOR TO ANY LANDSCAPE CONSTRUCTION.
8. PRIOR TO SPREADING TOPSOIL, LANDSCAPE CONTRACTOR SHALL INSPECT AND ACCEPT ALL BASE GRADES. ANY DEVIATION FROM LINE AND GRADE INDICATED ON THE GRADING PLAN SHALL BE CORRECTED BY EARTHWORK CONTRACTOR BEFORE PLACING ANY TOPSOIL.
9. BEFORE PLANT MATERIAL INSTALLATION BEGINS, STAKE LOCATIONS OF NEW PLANT MATERIAL AND NOTIFY LANDSCAPE ARCHITECT FOR APPROVAL. NOTIFY LANDSCAPE ARCHITECT ONE WEEK MINIMUM PRIOR TO TENTATIVE DATE OF STAKING.
10. CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT IF AREAS OF POOR DRAINAGE OR OTHER UNUSUAL SUBSURFACE CONDITIONS ARE ENCOUNTERED DURING EXCAVATION FOR PLANTING PITS.
11. ALL GRADING WORK SHALL BE COMPLETED PRIOR TO INSTALLATION OF PLANT MATERIAL AND LANDSCAPE MULCH.
12. ALL PLANT MATERIAL SHALL BE GROWN IN CLAY SOIL. ALL SHRUBS SHALL BE GROWN IN FIBRE POT CONTAINERS. ALL TREES SHALL BE NURSERY GROWN AND TRANSPLANTED USING THE BALL AND BURLAP METHOD.
13. ALL SHRUBS AND CONIFEROUS PLANTINGS SHALL BE INSTALLED IN CONTINUOUS PLANTING BEDS.
14. ALL SHRUB BEDS ADJACENT TO LAWN AREAS SHALL HAVE A SPADED EDGE BORDER, UNLESS METAL EDGE BORDER IS SPECIFIED. BORDER SHALL BE CUT 75mm DEEP AT A 45° ANGLE, SO THERE IS A CLEAR AND WELL DEFINED SEPARATION BETWEEN THE PLANTING BEDS AND SODDED AREAS.
15. CONTRACTOR SHALL SEED ALL AREAS DISTURBED BY CONSTRUCTION NOT DESIGNATED TO BE SODDED.
16. CONTRACTOR SHALL WORK OVER LAWN AREAS THAT HAVE REMAINED PARTIALLY INTACT. TOP DRESSING WITH SOIL, SCARIFYING, AND SEEDING TO FORM A SMOOTH, FULL, EVEN LAWN, FREE OF BARE SPOTS, INDENTATIONS, AND WEEDS.

DRAWING ISSUE RECORD

NO.	YY-MM-DD	DRAWING ISSUE RECORD
R0	07-20-23	ISSUED FOR CONSTRUCTION

PROJECT

MAIN & HENRY COMMUNITY CORNER - 715 MAIN STREET

CLIENT

CITY OF WINNIPEG

BrookMcIlroy/
ARCHITECTURE - LANDSCAPE ARCHITECTURE - URBAN DESIGN - PLANNING

UNIT 1, 91 ALBERT STREET
WINNIPEG, MB R3B 1G5
T. 204.515.0780

SHEET TITLE

PLANTING PLAN

PROJECT NO.	BID OPPORTUNITY NO.
21-013.01	581-2023

DESIGNED: TUI / SM

DRAWN: TUI / SM

DATE: 2023-07-18

SCALE: 1:100

SHEET NO.

L300