

## 65-2023 ADDENDUM 2

### MURRAY AVENUE WASTEWATER SEWER REPLACEMENT

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
BID/PROPOSAL**

ISSUED: January 31, 2023  
BY: Jordan Thompson  
TELEPHONE NO. 204 477 5381

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID/PROPOSAL AND SHALL FORM  
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

---

#### **FORM B: PRICES**

Replace: 65-2023\_Form\_B-Prices with 65-2023\_Addendum\_2\_Form\_B-Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R1): Revise A.3 description to read Connecting to Existing Manhole.

Form B(R1): Revise A.3(a) description to read 250mm.

#### **PART E – SPECIFICATIONS**

Delete: E5.3(b)(ii)

Delete: E5.3(b)(iii)

Delete: E5.3(b)(iv)

Add: E12.4.2(c) 250 mm Murray Ave WWS

- (i) Average Dry Weather Flow (ADWF): 3.5 l/s
- (ii) Peak Dry Weather Flow (PDWF): 12.5 l/s

Revise: E12.4.4(a) to read: Review the Environment Canada weather forecast with the Contract Administrator before each day of sewer connections.

Revise: E12.4.4(b) to read: Delay construction of connections and/or secure Works when the anticipated weather conditions are such that anticipated sewer flow will exceed the flow control measures provided.

Revise: E12.5(a) to read: Flow control measures necessary for installation or connection of wastewater sewers will not be measured for payment. It shall be incidental to connections to existing sewers.

Revise: E18.5.1 to read: The connection of the new 250 mm wastewater sewer shall be measured on a lump sum basis and paid for at the Contract Unit Price for "A.2 New Manholes ii) 1800mm diameter C/W 250 Internal Drop, Class 1 Backfill". The lump sum price shall include but not be limited to excavating the existing pipe, locating existing utilities, supporting existing utilities, cutting or coring the existing pipe opening, required new piping and connecting to the existing sewer, shoring, manhole sections, backfill, cast-in-place concrete works and

performing all operations necessary to complete the Works as specified and as indicated on the Drawings including all items incidental to the Works. Locating of the existing 1350 mm interceptor will be measured on a lump sum basis and paid for at the Contract Unit Price for "Locate Ex 1350 Interceptor Sewer".